BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT12835

APPROVED SCHEDULE - B

M.EE/BTP/BBMP/E-PMT/04/2014-15, Date:17.06.2014

Maintanance of ward and emergency works in ward no:11,kuvempu nagara,vidyaranyapura subdivision

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of GOPI REDDY K	
				In Figures	In Words
1	226.3	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. etc.,	Cum	234.4	Rupees Two Hundred Thirty Four and Forty Paise Only
2	0.18	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	4413.53	Rupees Four Thousand Four Hundred Thirteen and Fifty Three Paise Only
3	27.2	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3 lts confirming to IS 9103-1999 reaffirmed-2008 , machine mixed, concrete laid in layers not exceeding 15cms thic floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	5801.02	Rupees Five Thousand Eight Hundred One and Two Paise Only
4	24.48	KSRB 4.9.2: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery TMT Bars Fe 500 etc., complete and as per the directions of the Engineer-in-charge of the work	Qtl	7663.96	Rupees Seven Thousand Six Hundred Sixty Three and Ninety Six Paise Only
5	147.6	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials, labour etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	482.12	Rupees Four Hundred Eighty Two and Twelve Paise Only
6	31.8	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	208.85	Rupees Two Hundred Eight and Eighty Five Paise Only

Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

7	13.2	Flooring with 25mm to 40mm thick polished tandur blue stone slabs using mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	1066.44	Rupees One Thousand Sixty Six and Forty Four Paise Only
8	571.2	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S.square rods, or combination of M.S. flats and square rods as per approved design, drawning including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery etc., complete and as per the directions of the Engineer-in-charge of the work	Kgs	99.98	Rupees Ninety Nine and Ninety Eight Paise Only
9	1	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., complete and as per the directions of the Engineer-in-charge of the work	ach B\	1972.34	Rupees One Thousand Nine Hundred Seventy Two and Thirty Four Paise Only
10	50	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) etc., complete and as per the directions of the Engineer-in-charge of the work 0 to 50 m	Rmtr	320.69	Rupees Three Hundred Twenty and Sixty Nine Paise Only
11	50	50 to 100 m	Rmtr	419.2	Rupees Four Hundred Nineteen and Twenty Paise Only
12	50	100 to 150 m	Rmtr	466.36	Rupees Four Hundred Sixty Six and Thirty Six Paise Only
13	50	150 to 200 m	Rmtr	492.56	Rupees Four Hundred Ninety Two and Fifty Six Paise Only
14	50	200 to 250 m	Rmtr	570.11	Rupees Five Hundred Seventy and Eleven Paise Only
15	50	250 to 300 m	Rmtr	610.98	Rupees Six Hundred Ten and Ninety Eight Paise Only

Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

16	70	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	1388.6	Rupees One Thousand Three Hundred Eighty Eight and Sixty Paise Only
17	18	Providing 250mm dia PVC Pipe 6kg/cm etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	790.68	Rupees Seven Hundred Ninety and Sixty Eight Paise Only
18	1	Providing and fixing 160mm Borewell Cap etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	104.8	Rupees One Hundred Four and Eighty Paise Only
19	1	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 20 stage. etc., complete and as per the directions of the Engineer-in-charge of the work	Each	62968.41	Rupees Sixty Two Thousand Nine Hundred Sixty Eight and Forty One Paise Only
20	280	Supplying of ISI marked galvanized mild steel tube (continously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threaftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	393.0	Rupees Three Hundred Ninety Three Only
21	46	Heavy Duty Collar 50 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	136.24	Rupees One Hundred Thirty Six and Twenty Four Paise Only
22	570	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 49/ I No. 29-b(1) 4 Sqm mm of 56 strands 0.3mm dia Group - A etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	158.25	Rupees One Hundred Fifty Eight and Twenty Five Paise Only
23	1	Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap. Cable clips with bolts, nuts, valves guages etc., involoved in the job (Necessary GI pipe and specials with be supplied by the board at the site free of cost) etc., complete and as per the directions of the Engineer-in-charge of the work	No	3144.0	Rupees Three Thousand One Hundred Forty Four Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore-560092

24	1	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., complete and as per the directions of the Engineer-in-charge of the work	Each	298.68	Rupees Two Hundred Ninety Eight and Sixty Eight Paise Only
25	30	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class.etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	157.2	Rupees One Hundred Fifty Seven and Twenty Paise Only
26	30	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, In existing trencg/duct 6Sqmm to 16 Sqmm) etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	8.38	Rupees Eight and Thirty Eight Paise Only
27	25	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., complete (as per Civil SR etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	62.88	Rupees Sixty Two and Eighty Eight Paise Only
28	4	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	251.52	Rupees Two Hundred Fifty One and Fifty Two Paise Only
29	1	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	272.48	Rupees Two Hundred Seventy Two and Forty Eight Paise Only
30	1	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia,etc., complete and as per the directions of the Engineer-in-charge of the work	No	2043.6	Rupees Two Thousand Forty Three and Sixty Paise Only
31	6	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete and as per the directions of the Engineer-in-charge of the work	No.	104.8	Rupees One Hundred Four and Eighty Paise Only
32	1	Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads etc., complete and as per the directions of the Engineer-in-charge of the work.	Nos	1167.53	Rupees One Thousand One Hundred Sixty Seven and Fifty Three Paise Only
33	1	Providing and fixing in position PVC waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete and as per the directions of the Engineer-in-charge of the work	No	211.07	Rupees Two Hundred Eleven and Seven Paise Only
34	4	Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	83.84	Rupees Eighty Three and Eighty Four Paise Only

Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

35	1	Supplying shunt capaitors conforming to IS 2834, 3phase 400/440 volts grade for power factor improvement of rotating machinery, Capacitor in KVAR rating Nos. 2KVAR capacity with all lead and lift =, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	366.8	Rupees Three Hundred Sixty Six and Eighty Paise Only
36	1	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materiasl wiring complete as requireds 5 to 30 amps triple pole with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	1048.0	Rupees One Thousand Forty Eight Only
37	23400	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm etc., complete and as per the directions of the Engineer-in-charge of the work	Sq.Cm	0.35	and Thirty Five Paise Only
38	1	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. etc., complete and as per the directions of the Engineer-in-charge of the work	No.	11528.0	Rupees Eleven Thousand Five Hundred Twenty Eight Only
39	6.75	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	197.02	Rupees One Hundred Ninety Seven and Two Paise Only
40	20	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	164.54	Rupees One Hundred Sixty Four and Fifty Four Paise Only
41	6.75	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	63.93	Rupees Sixty Three and Ninety Three Paise Only
42	2	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads etc., complete and as per the directions of the Engineer-in-charge of the work	Each	1658.54	Rupees One Thousand Six Hundred Fifty Eight and Fifty Four Paise Only

Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

43	30	Providing and fixing sand cast iron soil waste and vent pipes 100mm dia with spun yarn soaked in cement slurry and cement mortar 1:2 including cost of materials, labour etc., complete and as per the directions of the Engineer-in-charge of the work	m	765.4	Rupees Seven Hundred Sixty Five and Forty Paise Only
44	4	Providing and fixing sand cast iron soil waste bends 100mm dia with access door, insertion of rubber washers 3mm thick bolts and nut, with spun yarn soaked in cement Slurry and cement mortar 1:2 including cost of materials, labour, testing etc., complete and as per the directions of the Engineer-in-charge of the work	Each	564.33	Rupees Five Hundred Sixty Four and Thirty Three Paise Only
45	3	Providing and supplying of Executive Extension Table-Celeon series of size 1810x422x952mm.(As per approved Data rate) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	59812.5	Rupees Fifty Nine Thousand Eight Hundred Twelve and Fifty Paise Only
46	2	Providing and supplying of executive High back Chair in Leatherite.(As per Approved Data rate) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	15122.64	Rupees Fifteen Thousand One Hundred Twenty Two and Sixty Four Paise Only
47	20	Providing and supplying of Cushion Chairs(As per approved Data rate) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	4359.68	Rupees Four Thousand Three Hundred Fifty Nine and Sixty Eight Paise
48	25	Neelkamal Plastic chairs etc., complete and as per the directions of the Engineer-in-charge of the work	No.	943.2	Rupees Nine Hundred Forty Three and Twenty Paise Only
49	1	Compouter Set with Printer etc., complete and as per the directions of the Engineer-in-charge of the work	No.	52400.0	Rupees Fifty Two Thousand Four Hundred Only
50	2	Almera etc., complete and as per the directions of the Engineer-in-charge of the work	No.	13624.0	Rupees Thirteen Thousand Six Hundred Twenty Four Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

Executive Engineer
Byarayanapura Division
Yelahanka, B.M.P.
Bangalore-560092